

**CENTRAL SHEEP & WOOL RESEARCH INSTITUTE,**  
**ARID REGION CAMPUS, BEECHWAL INDUSTRIAL AREA, SHRI GANGANAGAR ROAD, BIKANER**  
**(RAJASTHAN)- 334 006**

F.No.3(18)BK/NWPSI(MSF)/2013/Vol.I/ 1265

**REGISTERED MAIL**

Dated: 11.08.2014

Subject:- Quotation for *Renovation of two nos. rooms in farm area office for creation of AI Lab.*

Dear Sir,

On behalf of Director of Central Sheep & Wool Research Institute, I am to invite your quotation for *Renovation of two nos. rooms in farm area office for creation of AI Lab* work under mentioned G-SCHEDULE (Approximate cost of work Rs. 53,450) as follows:-

Sl.No.	Description of work	Approximate Quantity	Rate offered	Cost
01	Demolishing of old deteriorated floor including stacking of un-serviceable material	36.00 Sqm		
02	Making the opening in brick masonry wall by cutting masonry and making good	1.50 Sqm		
03	Repair to cement sand plaster 12mm to 20 mm in patches including cutting the patches in regular shape with good smooth finish C.M.(1:4)	5.70 Sqm		
04	Patch repair to cement concrete floor including digging out old floor in regular shape and removal of rubbish curing etc. complete in all respect	10.50 sqm		
05	Fixing of ceramic floor tiles of 1st quality confirming to Is:15622 laid on 20 mm thick bed of cement sand mortar (1:4) including jointing in white cement complete in all respect.	39.00 Sqm		
06	<b>FINISHING WORK</b>			
a	Removing white/colour wash by scraping ,sand papering the surface including misc. repair	123.60 Sqm		
b	Applying white cement based putty over plastered surface to prepare the surface even /smooth by rubbing etc.	111.80 Sqm		
c	Distempering with oil bound washable distemper of approved brand and manufacture to give an even surface In two or more coats	200.60 Sqm		
07	Painting with synthetic enamel paint of approved brand and quality to give an even shade. Item includes preparation of surface also In two or more coats	30.96 Sqm		
08	Applying ready mix primer of approved quality/brand on steel/galvanised iron	20.86 Sqm		
09	Painting with aluminum paint of approved quality and make In two or more coats	22.98 Sqm		
10	<b>ERECTION OF SHED AND CHAIN LINK FENCE</b>			
a	Excavation of earth in soil up to 1.5 m depth including disposal of surplus earth	4.25 Cum		
b	Shuttering with ply wood or steel shuttering including removal of form work	11.99Sqm		
c	Laying of C.C (1:3:6) including curing compaction etc. excluding the cost of shuttering	2.55Cum		
d	Steel work in built up tubular trusses including hoisting in position including welding, bolted etc.	187.60 Kg		
e	Laying of 6mm thick corrugated sheets roofing up to any pitch, fixing with j or L hooks, bolts, nuts 8mm dia G.I plain and bitumen washer complete.	52.00 Sqm		
f	Fixing of ridges or hips with 600 mm over all width with plain G.I sheet fixed with G.I. Jor L hooks ,bolts nuts etc.	4.50RM		
g	Erection of chain link fencing 50x50x 4mm thick including tightening with screw nut bolt etc.	112.00Sqm		
h	Fabrication of corral gates .item includes cutting, bending, straightening, welding of gates as per design.	100.00 Kg		
i	B/work in foundation in C.M.(1:6)including curing etc.	2.90 Cum		
j	Laying P.C.C.(1:5:10) using 40 mm thick crusher stone including compaction etc.	2.70 Cum		

k	Laying 40 mm thick C.C .floor (1:2:4) finished with a coat of neat cement with good finish	27.00 Sqm		
l	Applying 15 mm thick cement sand plaster in C.M(1:6) including racking of joints etc	28.88Sqm		
		Total Rs		

(Rupees \_\_\_\_\_ only)

Signature \_\_\_\_\_  
Name of the Firm \_\_\_\_\_  
Address \_\_\_\_\_


**TERMS & CONDITIONS:**

- Completion of work-** The work will be completed within a period of one month from the award of work failing which a penalty @ 1% of billed amount per week delay maximum to 10% of the billed amount of the work will be imposed.
- Work will be done in supervision of Incharge Estate.
- All the labour, T&P/scaffolding required will be arranged by the agency itself and no charges towards its handling, transportation will be paid.
- Rates will be given for labour charges only except item No.10(h) i.e. fabrication of corral gate.
- Please submit a copy of your registration for labour supply and copy of PAN with your offer.
- BILL:** PRE-RECEIPT BILL (in triplicate) may be prepared as per actual measurement.
- PAYMENT:** Payment will be made within reasonable time say within 30 days from the date of submission of bill after completion of work as per specification
- The rates quoted should be valid for 120 days from the date of opening of quotation.**
- There should be no cuttings/over writings. The cutting if any, should be duly attested. Unattested amended/overwritten figures will not be considered.
- In all matters of disputes, the decision of the Director/Head of this Institute shall be final and binding on the tenderer.
- EARNEST MONEY:** Earnest Money of Rs.2,000/- (Rupees Two Thousand only) must be deposited in the form of cash/demand draft/pay order in favour of "CSWRI UNIT ARC BIKANER".
- Successful tenderer will have to deposit 10% security money within three days from the receipt of information from this office.
- Quotation should be sent in a sealed cover and the cover containing the quotation must bear the words-  

**QUOTATION FOR CREATION OF AI LAB IN FARM OFFICE DUE DATE 01.09.2014**

Quotation received in an unsealed cover or received after the due date at 1.00 PM and those which are ambiguous are liable to be rejected.
- This Institute reserves the right to reject any or all the quotation (s) received without assigning any reason there of.**
- All communication must be addressed to the undersigned by DESIGNATION ONLY and not by name.
- This information is also available in our website [www.cswri.res.in](http://www.cswri.res.in)

Yours faithfully

  
(Md. Ayub)

Incharge Store & Purchase